


Ground Floor

(showing structure above)

| External Window Lintel Schedule | | | | | | | |
|---------------------------------|--------------------|--------|--|--|--|--|--|
| Number | Structural Opening | Length | Member Type | | | | |
| EL3WG1 | 1085mm | 1500mm | IG L1/S 100 or similar approved. | | | | |
| EL3WG2 | 1085mm | 1500mm | IG L1/S 100 or similar approved. | | | | |
| EL3WG3 | 1895mm | 2250mm | IG L1/S 100 or similar approved. | | | | |
| EL3WG4 | 635mm | 1050mm | IG L1/S 100 or similar approved. | | | | |
| EL3WG5 | 635mm | 1050mm | IG L1/S 100 or similar approved. | | | | |
| EL3WG6 | 1085mm | 1500mm | IG L1/S 100 or similar approved. | | | | |
| EL3WG7 | | | IG Bay Window lintel & post system or similar approved | | | | |
| EL3WG8 | | | IG Bay Window lintel & post system or similar approved | | | | |
| EL3WG9 | | | IG Bay Window lintel & post system or similar approved | | | | |
| EL3WG10 | 635mm | 1050mm | IG L1/S 100 or similar approved. | | | | |

| External Door Lintel Schedule | | | | | | |
|--------------------------------------|--------------------|--------|-----------------------------------|--|--|--|
| Number | Structural Opening | Length | Member Type | | | |
| EL3ED1 | 4112mm | 4650mm | IG L6/S 100 or similar approved. | | | |
| EL3ED2 | 932mm | 1350mm | IG L1/S 100 or similar approved. | | | |
| EL3ED3 | 932mm | 1350mm | IG L1/S 100 or similar approved. | | | |
| EL3ED4 | 2400mm | 2700mm | IG L1/HD 100 or similar approved. | | | |
| EL3ED5 | 3600mm | 4050mm | IG L6/S 100 or similar approved. | | | |
| EL3ED11 | 1838mm | 2250mm | IG L1/S 100 or similar approved. | | | |

| Internal Lintel Schedule | | | | | | |
|--------------------------|--------------------|--------|------------------------------------|--|--|--|
| Number | Structural Opening | Length | Member Type | | | |
| IL3ID1 | 910mm | 1350mm | IG HD Box 100 or similar approved. | | | |
| IL3ID2 | 910mm | 1350mm | IG HD Box 100 or similar approved. | | | |
| IL3ID3 | 910mm | 1350mm | IG Box 100 or similar approved. | | | |
| IL3ID4 | 680mm | 1050mm | IG Box 100 or similar approved. | | | |
| IL3ID5 | 910mm | | IG Box 100 or similar approved. | | | |
| IL3ID6 | 1600mm | 1950mm | IG HD Box 100 or similar approved. | | | |
| IL3ID7 | 910mm | 1350mm | IG Box 100 or similar approved. | | | |
| IL3ID8 | 910mm | 1350mm | IG Box 100 or similar approved. | | | |



STRUCTURAL NOTES

Please refer to all other design drawings by others.

Please refer to drg. no. 1035/300 for specification and notes relating to structural engineering designs.

Blockwork strengths to be as follows: -

From top of foundation to u/s of 1st floor - 7.3N/mm² From 1st floor and above

Span direction of infill members.

Movement joint in brickwork only (movement joints in blockwork by supplier).

Internal box lintels. External cavity lintels.

7.3N/mm² strength blockwork. 3.5N/mm² or 5.0N/mm² strength blockwork.

All lintels to be IG lintels of similar approved. Lintel sizes now confirmed.

Rev Amendment By Date SWF 30.05.11 P1 First issue. P2 Lintels sizes and type changed/confirmed. Layout titles added. SWF 22.07.11



Suite 116, Milton Keynes Business Centre, Foxhunter Drive, Linford Wood, Milton Keynes. MK14 6GD. t.01908 686855 f.01908 410333 www.cistec.net e.info@cistec.net



Drawing

STRUCTURAL ENGINEERING Proposed Superstructure - plot 3

Ground & First Floors

Group

46-48 Oakfield Road, Harpenden.

Scale 1:50 @ A1 Date 30.05.11

1035/305 p2